

SNO-ISLE LIBRARIES

Addendum 3

MILL CREEK LIBRARY TENANT IMPROVEMENTS | NO. 2024.03.22MCR

April 18, 2024

RFP Q & A CLARIFICATION

Sno-Isle Libraries received a request for clarification on two of the answers given to questions received in Addendum 2. Below are the original questions and the clarifying responses to the questions.

Q: On Restroom #104, the elevations on Drawing A702 Shows Tile Base on several walls that scale out to a 6" X 18" Tile. No Tile Base is specified and none of the tile products used even have a matching base. Please clarify what Tile Base is being used in Restroom #104.

Also, an Accent Tile is shown on A702 #1. The Finish Schedule on A700 doesn't show an Accent Tile for Restroom #104, just T-4 on the North, East, and South walls. Please clarify what wall tiles are being used in Restroom #104.

A: In Staff Restroom 104, wall tile is T-4 tile vertical stacked bond layout at South, East and North. Where wall covering or painted GWB is called for (West and South), tile base is to be half cut of T-3 (yielding a 6x24 base tile) horizontal layout.

Additionally, in RESTROOM 102, 103, and STAFF RESTROOM 114, wall tiles are T-1 horizontal stacked bond layout. Floor tile also is T-1 stacked bond. Accent wall is T-2, vertical stacked bond.

END OF ADDENDUM